


## 01 50 00 G – Airport Roadway Structure Load Limits



Construction vehicle gross vehicle weight is limited to the legal limits allowed on public roads.

Construction vehicles on the following airport roadway structures are limited to a maximum of four-axes:

- Departures Drive
- Arrivals Drive

Construction vehicles on the following airport roadway structures are limited to a maximum of five-axes:

- S 188<sup>th</sup> St Tunnel
- S 188<sup>th</sup> St Bridge
- Bridge 2 (Arrivals south recirculation ramp)
- Bridge 3 (Departures south recirculation ramp)
- Bridge 8 (S 170<sup>th</sup> St northbound)
- Bridge 9 (S 170<sup>th</sup> St southbound)
- Bridge 10 (S 160<sup>th</sup> St)
- Perimeter Road (Starling Drive)
- Bridge 19 (North Substation)
- Bridge 20 (S 170<sup>th</sup> St northbound)
- Bridge 21 (Doug Fox northbound)
- Bridge 22 (Return Ramp)